



Pavers on Pedistals.

Extruded Polystyrene Insulation.

Paraseal or Deckseal. (HDPE Side Up.
Temporary Tape at 1.5" (3.8cm) Lap Seams.
Use Permanent Seam Tape if Flood Testing
is Scheduled)

Concrete Roof Deck.

Paraseal. (See Section A)

Roof Deck With Pavers and Pedistals. (Also See RDP-03)

No.	Date	Description	By
TREMCO 3735 Green Road Beachwood, Ohio 44122 216-292-5000			
Project: Roof Decks / Planters			
Drawn by:	Scale:	Date:	Drafting/Revis. No.
J. Davis	Not To Scale	07/09/01	RDP-07