

TREMproof 260 applied at 100 wet mils over the Paraseal LG Benonite face.

Caisson areas that do not receive waterproofing will not be warranted by the mfg.

Nails

Termination Bar sealed with Dymonic 100

TREMDrain 1000

Bent Rebar

Shotcrete Wall

Paraseal LG with Bentonite side facing the installer

Superstop Waterstop

Exposed caisson face coated with Permaquik 200 Crystalline Waterproofing.

A Universal Tee Fitting with connected 4" PVC pipe must be replaced between each set of Caisson's in order to drain the water.

Paraseal LG starter strip to extend 6" min. below top of footing/mat slab.

All Paraseal LG Seams shall lap 4" Min.

Retained Earth

Augered concrete or formed concrete caisson

Paramastic, Grout, TREMproof 250GC - T, Earth or Dry Pack

Chemically stabilized and/or retained earth. Earth must not have voids over 1/2" in height or depth and shall not have voids over 1" in width.

NOTE: Paraseal products require a min of 24 PSF of compaction/confinement in order to function as designed.

NOTE: If the caisson is auger formed then it will need to be sack n patched in the areas where the metal termination bar will be installed prior to the Paraseal LG being terminated. Sack n Patch with a mixture of Non-Shrink Grout and Permaquik 100 Crystalline liquid additive.

**TREMCO**

www.tremcosealants.com

3735 Green Road \* Beachwood, OH 44122  
Phone : 866-209-2404 \* Fax: 216-766-5535

Detail: TREMproof TWS - INSTALLATION OVER AUGERED CAISSON

This detail is intended for conceptual purposes only.

Drawn by: MI

Checked by: JM

Scale: None

Sheet Number:

Date: 6/21/2016

File Name:

TWS -BSW-26

Rev #

00